



Republic of the Philippines
Office of the Solicitor General

Request for Quotation

To: _____
Tel. No.: _____
Fax No.: _____
Attention: _____

Date: November 22, 2022
Quotation #: PS 022-11-200
ABC: _____

Sir/Madam:

Please quote your lowest price on the items/s listed below, stating the shortest time of delivery and submit this from duly signed by your representative.

RODRIGO L. OJENAL
SAO, Administrative Division

To be filled-out by Supplier:

ITEM NO	ITEM & DESCRIPTION	QTY	UNIT	BRAND	UNIT PRICE	TOTAL PRICE
1	<p>SUPPLY OF LABOR AND MATERIALS, TOOLS AND EQUIPMENT FOR THE REPAIR OF OSG'S PADILLA HALL</p> <p><i>Repair of the OSG Padilla Hall located at the 9th Floor OSG Main Building 134 Amorsolo St. Legaspi Village, Makati City.</i></p> <p>TECHNICAL SPECIFICATION A. SCOPE OF WORKS</p> <p>1. Mobilization / Demobilization - 1 Lot</p> <p>2. Supply, Installation and Fabrication of modular cubicles with tables for Lawyers - 8 sets</p> <p>a. Size: (2.00mts.L1 - 2.00mts.L2 x 1.50mts.W1 x 0.80mts.W2 x 1.70mts.H)</p> <p>b. Color: For swatches approval</p> <p>c. Pattern: For swatches approval</p> <p>d. Electrical: LAN outlets, Duplex Power outlets and wiring</p> <p>3. Supply, Installation and Fabrication of modular cubicles with tables for Secretaries: 2 sets</p> <p>a. Size: (1.00mts.L1 - 1.00mts.L2 x 1.00mts.W x 1.20mts.H)</p> <p>b. Color: For swatches approval</p> <p>c. Pattern: For swatches approval</p> <p>d. Electrical: LAN outlets, Duplex Power outlets and wiring</p> <p>Supply, Installation and Fabrication of workstation for Front Desk Secretary: 1 set</p> <p>a. Size: Table: 2.40mts.L x 1.60mts.L2 x 1.10mts.W x 1.40mts.H</p> <p>b. Color: For swatches approval</p> <p>c. Paint color: For swatches approval</p> <p>d. Electrical: LAN outlets, Duplex Power and wirings</p> <p>Supply, Installation and Fabrication of ASG Room Modular Workstation with Side Cabinet (Pls. see attached layout): 1 set</p> <p>a. Size: Table - 2.20mts.L x 0.90mts.W x 0.75mts.H Side Cabinet - 1.8mts.L x 0.60mts.W x 0.60mts.H</p> <p>b. Area: At least 13sqm</p> <p>c. Fully painted inside and outside</p> <p>d. Paint color: For swatches approval</p> <p>e. Electrical: LAN outlets, Duplex Power and wirings</p> <p>Supply, Installation and Fabrication of SSS Room Modular Workstation with Side Cabinet (Pls. see attached layout): 1 set</p> <p>a. Size: Table - 2.20mts.L x 0.90mts.W x 0.75mts.H Side Cabinet - 1.8mts.L x 0.60mts.W x 0.60mts.H</p> <p>b. Area: At least 13sqm</p> <p>c. Fully painted inside and outside</p> <p>d. Paint color: For swatches approval</p> <p>e. Electrical: LAN outlets, Duplex Power and wirings</p> <p>Painting Works - 170sq.m.</p> <p>a. Color: For swatches approval</p> <p>b. Area: 170sq.m.</p> <p>Tiling Works - 100sq.m.</p> <p>a. Color: For swatches approval</p> <p>b. Size: 0.40mts. X 0.40mts.</p> <p>c. Are: 100sq.m.</p> <p>Preparation of copies of As-Built Plans for Architectural and Electrical including</p> <p>a. Architectural - 7 sets</p> <p>b. Electrical - 7 sets</p> <p>Drywall Partition - 1 Lot</p> <p>Kitchen Ceiling Works - 1 Lot</p> <p>Hauling of Debris Materials - 1 Lot</p> <p><i>Note: All materials, tools, and equipment is provided by the suppliers. Supplier is also responsible for permits, and licenses, if necessary or required.</i></p>	1	LOT			